

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>33</u> , T. <u>47</u> N. S., R. <u>34</u> E. W.		<u>6, 9, 1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner 6: Not set on original survey nor subsequently apparently.
- Corner 9: Not set on original survey nor subsequently apparently.
- Corner 1: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner 6: Established on section subdivision.
- Corner 9: Established on section subdivision.
- Corner 1: Established on section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |
|---|---|
| Corner 6: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap. | Corner 1: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap. |
| 3" Sugar N75E 9.7 ft. 1/16S,BT                            | 12" White Pine N82W 24.5 ft. 1/16S,BT                     |
| 6" Sugar S12W 13.3 ft. 1/16S,BT                           | 16" White Pine N50E 21.2 ft. 1/16S,BT                     |
| 5" Maple N25W 11.0 ft. 1/16S,BT                           | 9" White Pine S05W 17.5 ft. 1/16S,BT                      |
| Corner 9: Set 1" I.D.x24" Iron Pipe                       |   |
| 3" Sugar South 10.5 ft. 1/16S,BT                          |   |
| 4" Sugar S82E 28.4 ft. 1/16S,BT                           |   |
| 7" Sugar N35W 31.0 ft. 1/16S,BT                           |   |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-12-79

CHIEF OF SURVEY PARTY  
Keith L. Sackett  
 REGISTERED LAND SURVEYOR  
 Michigan Dept. of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006