

BARAGA Co

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. S. R. 34 E. W.	E12, F11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E12: Original monument and accessories not found. Found old beaver tree on old E-W winter road about one chain south and old marks on 6" cedar N05W 11.6 ft.
 Corner F11: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E12: Restored corner 11-29-78 at intersection of old marks. Position fits good with other corners in area.
 Corner F11: Restored on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E12: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap.	Corner F11: Set 1" I.D.x36" Iron Pipe with 4" aluminum cap.
7" Cedar East 39.9 ft. 1/4S,NBT	9" Cedar N37E 13.5 ft. 1/4S,NBT
6" Cedar N05W 11.6 ft. 1/4S,NBT	5" Sugar S38E 21.6 ft. 1/4S,NBT
8" Cedar S15W 50.8 ft. 1/4S,NBT	6" Balsam S78W 5.5 ft. 1/4S,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

