

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

BARAGAN Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47N</u> N. S., R. <u>34W</u> E. W.	<u>M5, L5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 19, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M5: Original monument and accessories not found. Found old blazes in area.

Corner L5: Original monument and accessories not found. Found 1-1/2" I.D. by unknown length iron pipe witnessed by M.S.H.D.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M5: This corner restored by land calls in four directions. Fits good with other corners in area.

Corner L5: Restored at iron pipe fits good with corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M5: Set 1" I.D. x 36" iron pipe.

6" Sugar	S27°W	28.8 Ft.	S 13, NBT
7" Sugar	S78°E	28.2 Ft.	S 18, NBT
14" Maple	N80°W	42.5 Ft.	S 12, NBT

Corner L5: 1-1/2" I.D. iron pipe

6" Maple	N51°W	16.4 Ft.	1/4 S, NBT
12" Maple	S35°E	26.4 Ft.	1/4 S, NBT
14" W. Pine	S25°W	50.8 Ft.	1/4 S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2/6/80

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

