

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47N N. S., R. 34W E. W.	K5, K7
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K5: Original monument and accessories not found.

Corner K7: Original monument and accessories not found. Found post set by J. P. Smallwood M.S.H.D. Found Northern Paper Mills Location Poster.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K5: Restored 6-7-79 from M.S.H.D. Stationing and R.O.W. Markers.

Corner K7: Restored 6-22-79 at M.S.H.D. Post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K5: Set 1" I.D. x 36" iron pipe with 4" aluminum cap in Sphagnum Moss area. No available NBT's. Corner falls 45.15 ft. west of US 141 and Sta. 1640 + 13.83. R.O.W. Marker West 54.8 Ft.

Corner K7: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 18" W. Pine N52°W 21.4 Ft. S 14, NBT
 12" Maple S50°W 4.8 Ft. S 23, NBT
 8" Balsam S87°E 12.4 Ft. S 24, NBT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE 2/6/80

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-10-80
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 26, 1971
 REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET