

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Baraga

(BARAGA COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>47</u> N. <u>X</u> , R. <u>34</u> <u>X</u> W.	<u>G-10, G-9</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G-10: Found possible bearing tree stump Cedar S56E 9 links. Fits with other corners and land calls.

Corner G-9: Found remains of old square post set by Northern Paper Mills around 1930. Corner fits good with land ties to east, north, south, and corner to west.

Northern Paper Mills location poster on 5" spruce S45E 6.6 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G-10: Reestablished from possible bearing tree. Fits good with other corners.

Corner G-9: Reestablished at post hole from old square post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-10: Set 1" I.D. x 30" I.P. with 4" aluminum cap.

7" Cedar S19W 8.8 ft., 1/4S, NBT

6" Cedar N58W 11.4 ft., 1/4S, NBT

10" Balsam S68E 19.1 ft., 1/4S, NBT

Corner G-9: Set 1" I.D. x 30" I.P. with 4" aluminum cap.

4" Spruce N46E 14.8 ft., S22, NBT

5" Spruce S45E 6.6 ft., S27, NBT

8" Spruce S46W 33.4 ft., S28, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-3-80

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

