

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(BARAGA COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>47</u> N. E. R. <u>34</u> W.	<u>E-10, E-9</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 23, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E10: Original monument and accessories not found. Found old post set by unknown person. 1946 Northern Paper Mills location poster facing corner. Many old blazes in area.

Corner E-9: Original monument and accessories not found. Found Northern Paper Mills iron pipe with brass cap set from original bearing tree.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E-10: Reestablished at old post. Fits good with other corners in area.

Corner E-9: Reestablished at monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E-10: Set 1" I.D. x 36" I.P. with 4" aluminum cap.
 8" Sugar N65W 4.6 ft., 1/4S, NBT
 6" Sugar N60E 17.3 ft., 1/4S, NBT
 9" Sugar S10W 2.4 ft., 1/4S, NBT

Corner E-9: 1" I.D. x unknown length iron pipe with brass cap.
 14" Ash N 8W 23.2 ft., S20, NBT
 5" Y. Birch N44E 4.2 ft., S21, NBT
 3" Sugar S20W 14.1 ft., S29, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Department of Natural Resources

DATE 9-3-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

