

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

(BARAGA COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. R. 34 W.	F-10
2. PROPERTY CONTROLLING IN SECTION 28	T. 47 N. R. 34 W.	8, 9
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 24, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner F-10: Not set on original survey nor subsequently, apparently.
 - Corner 8: Not set on original survey nor subsequently, apparently.
 - Corner 9: Not set on original survey nor subsequently, apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner F-10: Established during section subdivision.
 - Corner 8: Established during section subdivision.
 - Corner 9: Established during section subdivision.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner F-10: Set 1" I.D. x 30" I.P. with 4" aluminum cap.
 - 9" Maple N04W 23.4 ft., 1/4S, BT
 - 9" W. Birch N47E 5.2 ft., 1/4S, BT
 - 6" W. Birch S55W 6.4 ft., 1/4S, BT
 - Corner 8: Set 1" I.D. x 30" I.P. with 4" aluminum cap.
 - 9" Cedar N60E 3.0 ft. } Upper and lower blaze but not
 - 7" Cedar N85W 17.5 ft. } scribed as of 06/24/80
 - Corner 9: Set 1" I.D. x 30" I.P.
 - 9" Maple S60W 22.7 ft., 1/16S, BT
 - 4" Sugar S43E 15.0 ft., 1/16S, BT
 - 6" Sugar N18W 17.2 ft., 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE June 24
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

