

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>X.</u> , R. <u>34</u> <u>X.</u> W.	<u>K4</u>
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	, T. <u>47</u> N. <u>X.</u> , R. <u>34</u> <u>X.</u> W.	<u>7, 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 14, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner K4: Original monument and accessories not found.**
  - Corner 7: Not set on original survey nor subsequently apparently.**
  - Corner 14: Not set on original survey nor subsequently apparently.**
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner K4: Restored midway and on line between section corners north and south.**
  - Corner 7: Established midway and on line between corners north and south.**
  - Corner 14: Established midway and on line between corners north and south.**
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |   |  |
|---|--|
| <p><b>Corner K4:</b> Set 1" I.D.x36" iron pipe with 4" alum. cap.<br/>                 11" Y. Birch N82E 18.1 ft. 1/4S,NBT<br/>                 6" Sugar S41E 27.7 ft. 1/4S,NBT<br/>                 7" Sugar N22W 22.3 ft. 1/4S,NBT</p> <p><b>Corner 7:</b> Set 1" I.D.x32" iron pipe with 4" alum. cap.<br/>                 12" Sugar N27W 6.6 ft. 1/16S,BT<br/>                 9" Sugar S52W 9.4 ft. 1/16S,BT<br/>                 14" Y. Birch N79E 13.5 ft. 1/16S,BT</p> | <p><b>Corner 14:</b> Set 1" I.D.x36" iron pipe with 4" alum. cap.<br/>                 4" Sugar S21E 22.0 ft. 1/16S,BT<br/>                 14" W. Pine N89E 15.7 ft. 1/16S,BT<br/>                 7" W. Birch S55W 28.3 ft. 1/16S,BT</p> |
|---|--|

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-28-82  
CHIEF OF SURVEY PARTY  
**Keith L. Sackett**  
 Michigan Registered Land Surveyor  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

