

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BARAGA COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> ^{N.} X _{W.} , R. <u>34</u> ^{E.} X _{W.}	<u>K6</u>
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>47</u> ^{N.} X _{W.} , R. <u>34</u> ^{E.} X _{W.}	<u>14, 7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} _{S.} , R. _____ ^{E.} _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Keith L. Sackett**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 27, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner K6: Original monument and accessories not found.**
 - Corner 14: Not set on original survey nor subsequently apparently.**
 - Corner 7: Not set on original survey nor subsequently apparently.**
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner K6: Restored midway and on line between section corners north and south.**
 - Corner 14: Established midway and on line between corners north and south.**
 - Corner 7: Established midway and on line between corners north and south.**

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|---|---|
| <p>Corner K6: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 12" Sugar S57W 24.1 ft. 1/4S,NBT
 12" Sugar N62W 16.0 ft. 1/4S,NBT
 8" Sugar N54E 40.1 ft. 1/4S,NBT</p> <p>Corner 14: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 8" Sugar N47E 14.6 ft. 1/16S,BT
 6" Sugar S25E 23.3 ft. 1/16S,BT
 14" Cedar S29W 3.4 ft. 1/16S,BT</p> | <p>Corner 7: Set 1" I.D.x32" iron pipe with 4" alum. cap.
 6" Balsam S07E 33.1 ft. 1/16S,BT
 4" Balsam S07W 35.9 ft. 1/16S,BT
 Row Marker N19E 27.8 ft. 1/16S,BT</p> |
|---|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82

CHIEF OF SURVEY PARTY

MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Michigan Dept. of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006