

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

(County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	K3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T 47N R 34W	6
	S T 47N R 34W	5
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

5 July 27, 1994

6 July 26, 1994

I, Stephan J. Szyszkoski, in a field survey on K3 March 23, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereto as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. Corner monumented in 1951 by Dean C. DeLaMater, RLS with a 1" I.D. iron pipe and 4" brass cap placed from two original bearing trees. New bearing trees marked - 10" Hemlock S33E 59 links, 12" hemlock S18W 50 links, 14" Hemlock N38E 74 links. Northern Paper Mills records dated 1953 show that the 1951 monument was recovered as described and two additional NBTs were marked - 12" Hemlock S51E 13 links, 8" Hemlock S42W 4 1/2 links. The NPM record states original BT Y. Birch 24' S44E 22, I.W. very plain. Tree is green in fair condition. Old marks and Reg's. The 1951 monument was also recorded by the Michigan Dept. of State Highways and Transportation in 1958.

(6-Sec. 1) Northeast 1/16 corner, Sec. 1. Corner not established in the original survey. Found no subsequent record.

(5-Sec. 1) North 1/16 corner, Sec. 1. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) Found and accepted the 1951 monument - a 1" I.D. iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet - at record bearing and distance from the 3 1951 NBTs. The 10" hemlock is now a dead stub S30E 39.1', the other two hemlocks are in good condition with blazes overgrown: 14" dia. S20W 32.7', re-marked "S11 NBT", 16" dia. N39E 48.1' re-marked "S1 NBT". The NPM Hemlock SE was found to be a 22" Hemlock S50E 7.9' to face. The 8" NPM Hemlock was found a 12" dia. tree with old overgrown blazes S47W 27.0' (41 links). The original Y. Birch BT was found a dead stub S35E 22 links. No scribing is visible but old rotted blaze and axe marks were plain. Marked one new bearing tree as described below.

(6-Sec. 1) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners, all monumented. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner falls in an open cedar marsh about 30' South of the N'y margin and about 50' East of the W'y margin. A 9" dead cedar snag with a location poster facing the corner is S60W, 18.4' distant.

(5-Sec. 1) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between Center of Section 1318.38' South and quarter corner 1303.19' North, being 20 chains, proportionate to the original record, north of the center. At the position for the corner I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast alumin MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Found 1" pipe with 4" brass cap. Blazed and scribed the following bearing trees:
 11" Cedar N76W 39.9' "S2 NBT"
 N. edge of open marsh, South 40'
 Found dead cedar stub with location poster N30E 14'.
 Bearings are magnetic. Decl. 2.5 deg W.

(6) Set a 1" pipe with 4" MDNR cap. Blazed and scribed the following bearing trees:
 5" Cedar S60E 19.2' "1/16S BT"
 11" Cedar N02W 57.7' "1/16S BT"
 13" Cedar N38W 40.3' "1/16S BT"
 10" Cedar N64W 53.0' "1/16S BT"
 Set a 3" squared cedar post adjacent. Bearings are magnetic. Decl. 2.5 deg W.

(5) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following bearing trees:
 5" Maple S09W 11.0' "1/16S BT"
 8" Sugar S62W 11.3' "1/16S BT"
 4" Sugar N52W 12.3' "1/16S BT"
 10" Maple N30E 25.4' "1/16S BT"
 Bearings are magnetic. Decl. 2.5 deg W.

Signed by Stephan J. Szyszkoski

Date 8-16-94

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division

