

85.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

(County)	Located In:	Corner Code //
1. Public Land Survey	T 47N R 34W	A1
	T 47N R 34W	B1
	T R	
	T R	
2. Property Controlling in Section	S 6 T 47N R 34W	I
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on June 30, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(A1) Northwest corner of the township. Corner previously re-monumented in 1966 by Billy D. Buckler L.2-P.265 as follows: Placed 1" pipe with 4" aluminum cap from two original witnesses, a cedar...and a hemlock stump... 1966 NBTs: 7" Sugar N50E 30.5', 7" Sugar N67W 15.0', 14" Y. Birch S04W 43.8'. Corner recorded in 1988 by Richard L. Drahn L.4-P.186 who accepted Buckler's pipe and marked the following: 8" Sugar N17W 36.35', 6" Sugar N02E 33.13', 6" Sugar N79E 18.41', 6" steel sign post S57W 1.45'.

(B1) Quarter corner common to Section 6 T47N-R34W and Section 31 T48N-R34W. Corner re-monumented in 1966 by Billy D. Buckler with a 1" pipe with 4" aluminum cap placed at an old stake bottom found at record bearing and distance from the original bearing trees. Buckler's NBTs: 9" Hard Maple N49W 28.5', 9" H. Maple S43E 8.6'.

(1-Sec. 6) West 1/16 between sections 6 T47N-R34W and 31 T48N-R34W. Corner not established in the original survey. Corner position determined in 1966 by Billy D. Buckler as being at an old fence corner. 1966 NBTs: 14" Hard Maple N18W 16.4', 14" Hard Maple S70E 5.0'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A1) Found the corner marked by a 1" pipe with 4" aluminum cap placed by Buckler in 1966. The monument has been disturbed and is leaning over. Straightened the monument to a vertical position so as to be in accord with 2 of the 3 1966 NBTs: Sugar to the NE and Y. Birch to the SW. Re-measured all recorded NBTs as shown below.

(B1) Found and accepted a 1" iron pipe with a 4" aluminum cap placed by Buckler at record bearing and distance from the remains of his two 1966 NBTs, both dead and down. Marked four new bearing trees as described below.

(1-Sec. 6) Found but did not accept Buckler's 1966 monument, at record bearing and distance from his NBTs. Determined the position for the corner to be 20 chains proportionate to the original record west of the 1/4 corner between sections 6 and 31, and on a straight line between the 1/4 corner and the northwest corner of township 47N-R34W. Found the distances between original corners east and west to be 1339.86' and 1163.67' respectively. Removed the monument placed in 1966, which I found to be 91' east and 1' south of the 1/16 corner, and monumented the corner position with a 1" I.O.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, projecting 12".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A1) Found 1" iron pipe with MDNR cap.

The 1966 NBTs all in good condition:

7" Sugar N46E 30.5'

7" Sugar N68W 15.5'

14" Y. Birch S05W 43.8'

The 1988 NBTs (all with measuring nails, blazes, scribing, and signs):

8" Sugar N17W 36.60'

6" Sugar North 33.26'

4" Sugar N80E 17.97'

A metal sign post S67W 1.8'

Bearings are magnetic.

(B1) Found a 1" pipe with 4" MDNR cap.

Blazed and scribed the following new bearing trees:

8" Sugar S37E 12.2' "1/4S NBT"

8" Sugar N35W 32.5' "1/4S NBT"

12" Maple N07E 40.7' "1/4S NBT"

11" Sugar S34W 36.1' "1/4S NBT"

Set a squared 3" sugar post adjacent.

Corner falls 40 links west of a logging road. Bearings magnetic.

(1) Set a 1" pipe with a 4" MDNR cap.

Blazed and scribed the following bearing trees:

7" Sugar N27E 18.6' "1/16S BT"

10" Sugar N36W 26.4' "1/16S BT"

8" Sugar S27W 19.3' "1/16S BT"

7" Sugar S57E 18.6' "1/16S BT"

Set a 5" squared cedar post adjacent.

Bearings are magnetic.

Signature: Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 7-13-94

