

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>19</u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
2. Property Controlling in Section	S <u>26</u> T <u>47N</u> R <u>34W</u>	<u>12</u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

19 Jun 21 2001  
 12 Aug 20 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9									●				
10	30	29	28	27	26	25				●			
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(19) Corner common to Sections 22-23-26-27. 1951: Remonumented in the original position by Dean C. DeLaMater RLS. 1" pipe with 4" brass cap. 10" Cedar N77W 29 links, 8" Cedar S58E 35 links.  
 (12-Sec. 26) South 1/16 corner, Section 26. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(19) Recovered the 1951 monument, a 1"ID iron pipe with 4" brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1951 witnesses, both in good condition. Left the monument in place and marked two new accessories as described below.  
 (12-Sec. 26) Established the corner midway and on a straight line between Quarter corner 1316.51' south and Center of Section 1316.51' north.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(19) 1"ID iron pipe with 4" brass MDOC tablet. Blazed and scribed the following new bearing trees: 7" Cedar N18E 17.2'      "S23 NBT" 7" Cedar S22W 34.0'      "S27 NBT" Bearings are magnetic. Distances are to notch in lower blaze.	(12) 1"IDx32" iron pipe with 4" alum. MDR tablet. Blazed and scribed: 6" Sugar N69E 17.9'      "1/16S BT" 10" Maple S35E 34.4'      do 14" W.Pine S65W 36.9'      do 7" Maple N62W 26.6'      do Set sq'd maple post adjacent. Bearings are magnetic. Distances to notch in lower blaze.
---	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/24/01

For the Michigan Department of Natural Resources - Office of Property Management