

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga	Located In:	Corner Code #
(County)		
<b>1. Public Land Survey</b>	T <u>47N</u> R <u>34W</u>	<u>J10</u>
	T <u>47N</u> R <u>34W</u>	<u>L11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
<b>2. Property Controlling in Section</b>	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
<b>3. Miscellaneous Property in Sec.</b>	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

L11 Aug 13 2001  
 J10 Aug 15 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		●		25		
11												●	
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(J10) Center of Section 26. Not established in the original survey.  
 (L11) Quarter corner common to Sections 25-36. 1852: Established by I.B.Searles midway and on a line between Section corners 40.20 chains east and west. Set wood post. Cedar 10 S74W 9L, Cedar 16 N39E 30L. 1958: John P. Smallwood notes for Michigan Dept. of Transportation: Found 4" cedar post. 6" Willow N10E 22.50', 4" Willow S75W 13.10', 2" Balsam S20W 25.20'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(J10) Established the corner at the intersection of straight lines connecting opposite quarter corners.  
 (L11) The original post and accessories were not recovered. Found the 1958 wood post, down, partially rotted, point in good condition and set firmly, in accord with Smallwood's measurements to the State Highway. The 1958 witnesses were not recovered. Reestablished the corner proportionate to the US record, on a line of mean true bearing and midway between section corners 2639.08' east and west. From the corner monumented, I found a 1.25" ID iron pipe, not of record, bearing S20W 22.05' distant. At the position of the 1958 post point I place a 9" iron spike which bears from the corner N78 deg. 41'44"W (MCS83 grid bearing), 6.63' distant.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J10) 1" IDx32" iron pipe with 4" alum.	(L11) 1" IDx32" iron pipe with 4" alum.
MDNR tablet. Blazed and scribed:	MDNR tablet. Blazed and scribed:
12" Y. Birch N46E 19.3'	9" B. Ash N24E 47.6'
7" Sugar S87E 14.2'	11" B. Ash S53E 36.2'
12" Sugar S60W 16.5'	8" B. Ash S31W 35.6'
8" Y. Birch N41W 40.7'	10" B. Ash S72W 20.0'
Set squared cedar post adjacent.	Set squared cedar post adjacent.
Bearings are magnetic. Distances to notch in lower blaze.	Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 10/24/01  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Office of Property Management