

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located in:

Corner Code #

1. Public Land Survey

T47N R 34W I10
T47N R 34W K11
T R
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

K11 Aug 20 2001
I10 Aug 15 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(I10) Quarter corner common to Sections 26-27. 1852: Established by Z.B.Searles on a line between Section corners 40.015 chains north and south. Set wood post. Cedar 6 S75W 16-L, Fir 6 N80E 17 L.

(K11) Corner common to Sections 25-26-35-36. 1852: Established by Z.B.Searles, whose measure to adjacent section corners is 80.06 chains north, south, and west, and 80.40 chains east. Set wood post. Cedar 16 S30E 11 L, Spruce 10 N18W 7 L. 1958: John P. Smallwood notes for the Michigan Dept. of Transportation: Found 3" cedar post. 6" Pine stump N35W 13.10', 6" Pine stump West 29.15'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I10) The original post and accessories were not recovered. Reestablished the corner on a line of mean true bearing between Section corners 2630.19' north and south.

(K11) The original post and accessories were not recovered. The 1958 post and accessories were not recovered. The corner now lies within a disturbed area, under the surface of the Net River impoundment. Reestablished the corner by double proportionate measurement to the original record noted above. The corner position was not monumented. Established two witness corners, 1) 50.00' east and 2) 130.00' north of the corner position, on the respective section lines, and monumented both with 1"IDx32" iron pipe capped with 4" alum. MDNR tablets, appropriately stamped. Witnesses below are to the WC 130.00' north. Placed a squared post adjacent to the E'ly WC but there were no trees near so I made no accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I10) 1"IDx32" iron pipe with 4" alum.

MDNR tablet. Blazed and scribed:

10" Cedar N59E 19.3' "1/4S NBT"

13" Cedar S55E 38.7' do

7" Cedar S23E 42.4' do

12" Cedar S86W 25.7' do

Set squared cedar post adjacent.

Bearings are magnetic. Distances are to notch in lower blaze.

(K11) 1"IDx32" iron pipe with 4" alum.

MDNR tablet, stamped appropriately,

located on the section line 130.00'

north of the position for the corner.

Blazed and scribed:

2" Tamarack S55E 60.6' "WC BT"

3" Tamarack N21W 34.2' do

No other trees available. Set sq'd cedar post adjacent. Bearings magnetic.

Dist. to notch in lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/24/01

For the Michigan Department of Natural Resources - Office of Property Management