

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>J9</u>
	T <u>47N</u> R <u>34W</u>	<u>J11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

J11 Aug 02 2001
 J9 Jun 21 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9									●			
10	30		29		28		27		26		25	
11									●			
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

(J9) Quarter corner common to Sections 23-26. 1951: Remonumented in the original position by Dean C. DeLaMater RLS, from original 8T in good condition. 1" pipe with 4" brass cap. 6" S.Maple S28W 7 links, 4" S.Maple N75E 45 links. 1953: The 1951 monument was recovered by Wickman and Peryam of Northern Paper Mills Forestry Division. New witness 6" Sugar S10W 28.8'.
 (J11). Quarter corner common to Sections 26-35. 1852: Established by L.B.Searles midway and on line between Section corners 40.03 chains east and west. Set wood post. Spruce 8 S54E 14, Spruce 8 N40W 8.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J9) Recovered the 1951 monument, a 1" ID iron pipe with 4" brass MI Dept. of Conservation tablet, appropriately stamped, in good condition, and at record bearing and distance from both 1951 NBTs and the 1953 NBT, all green. Left the monument in place and made new witnesses.
 (J11) Original post and accessories were not recovered. Reestablished the corner proportionate to the US record, midway and on a line of mean true bearing between Section corners 2627.91' east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J9) Found 1" ID iron pipe with 4" brass MDOC tablet. Blazed and scribed: 8" Sugar N60W 7.0' "1/4S NBT" 10" Sugar N44E 16.6' do The NBTs of record: 11" Sugar N75E 29.7' blazes overgrown 12" Sugar S16W 28.8' scribing visible 10" Sugar S28W 4.6' in poor condition Squared cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.	(J11) 1" IDx32" iron pipe with 4" alum. MDRR tablet. Blazed and scribed: 12" Cedar N30E 9.6' "1/4S NBT" 9" Cedar S55E 29.2' do 9" Cedar S13W 4.4' do 10" Cedar N46W 5.5' do Set squared cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/24/01

For the Michigan Department of Natural Resources - Office of Property Management