

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga  
 \_\_\_\_\_  
 (County)

Located in:

Corner Code #

- |                                    |   |   |       |
|------------------------------------|---|---|-------|
| 1. Public Land Survey              | T | R | J3    |
|                                    | T | R | E5    |
| 2. Property Controlling in Section | S | T | _____ |
|                                    | S | T | _____ |
| 3. Miscellaneous Property in Sec.  | S | T | _____ |
|                                    | S | T | _____ |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jul 03 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	10	17		16		15		14		13		
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(J3) Quarter corner common to Sections 2-11. Northern Paper Mills land corner record dated March 1953 by N.J.Peryam and S.R.Wickman states: Orig. 8.T.s Hem. 16 N18E 2, Sug 12 S81W 18. Sept 1930: Cole and Sillers found both 8.T.s & stubs. March 1932: Cole and Ellison Found 8.T. 24" Hem stub & sq. 8" Bir. Jan 1947: Mitchell & Peryam found stub of Hem. 8.T. Post. Old Reg's Sq 10" Bir. N.P.M. L.M. March 1953: Wickman & Peryam found Hem. stub down no I.M. Sq'd 10" Bir. Intersection old lines. N.P.M. L.M. Set pipe and brass cap from down Hem stub. Y. Bir 16" S18W 40 links, Sug. 12" N20W 19.5 links.  
 (E5) Corner common to Sections 8-9-16-17. Remonumented in 1966 and recorded in 1967 by Billy D. Buckler RLS: " This corner replaced at wood post set by unknown persons. Found several old blazes facing corner location. 1" pipe with 4" aluminum cap. 20" W.Pine N62W 59.8', 14" Soft Maple S40E 21.4'."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(J3) Recovered the 1953 monument, a 1" ID iron pipe with a 2.25" dia. brass Northern Paper Mills cap, appropriately stamped, in good condition, and at record bearing and distance from the remains of the 1953 witnesses. The Y.Birch is a dead stub with scribing plain. The Sugar is a windthrown root mass. Accepted the monument as a careful and faithful perpetuation of the position of the original corner and made new witnesses as described below.

(E5) Recovered the 1966 monument in good condition and at record bearing and distance from the 1966 witnesses. The W.Pine is a cut stump with meas. notch visible. The Maple is 18" DBH and in good condition with overgrown blazes. No land survey was made here this date. This record is made solely to perpetuate the 1966 position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J3) Fd. 1" iron pipe with brass MPH cap. Blazed and scribed the following:	(E5) Found 1" ID iron pipe with 4" alum. MDOC cap. Blazed and scribed:
7" Sugar S34W 8.3' "1/4S NBT"	12" Sugar S37W 5.9' "S17 NBT"
5" Sugar N51W 31.4' do	6" Sugar N33W 32.4' "S8 NBT"
14" Sugar N05E 10.1' do	16" Sugar N62E 14.5' "S9 NBT"
8" Y.Birch S78E 31.8' do	18" Maple S35E 21.4' (1966 NBT)
Placed a sq'd cedar post adjacent.	Sq'd sugar post adjacent. Bearings are
Bearings are magnetic. Distances are to notch in lower blaze.	magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/15/01

For the Michigan Department of Natural Resources - Forest Management Division