

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>D1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>5</u> T <u>47N</u> R <u>34W</u>	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

May 13 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D1) Quarter corner common to Section 5 T47N-R34W and Section 32 T48N-R34W. 1966: Record of Frank J. Bray, RLS states: "This corner was replaced from W.Pine Stump (W.Pine 34" N25E 15 links) rotted badly seems to check with swamp edges to East and West". Set 1" Iron Pipe with 4" aluminum cap. New witnesses: 8" W.Birch N79W 12 links, 7" W.Pine S22E 33.5 links.
 (8-Sec. 5) West 1/16 corner, Section 5. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D1) The 1966 monument and accessories were not recovered and have been destroyed by gravel mining operations. I reestablished the corner by reference to Corner #2 of Section 5, E1, and F1, all previously remonumented and recorded by Mr. Bray. Specifically, I monumented the corner at the weighted mean of two positions obtained by extrapolating from Mr. Bray's record: He states that 1) Corner #2, Sec. 5 was midway and on line between E1 and D1, and that 2) corner E1 was remonumented midway and on line between F1 and D1. The weighted mean position satisfies the first condition to within 0.8' and the second to 1.6'.
 (8-Sec. 5) Established the corner midway and on a straight line between Quarter corner 1317.89' west and Center of Section 1317.89' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D1) Set 1" IDx32" I.pipe with 4" alum. MDNR cap driven to 0.2' below the grade in the gravel pit floor. Placed squared cedar post adjacent 2' N'y. A 1" ID iron pipe with 4" alum. cap stamped "FORD" bears N 1 deg. 45' W (true) 45.06' distant. No nearby trees for marking. Copy of survey drawing on file at Michigan D.N.R. office in Baraga.	(8) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 10" Sugar N84E 8.9' "1/16S 8T" 9" Sugar S35E 19.8' do 7" Sugar S70W 18.0' do 6" Sugar N17W 28.7' do South 58' +/- center of gravel rd. Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/1/04

For the Michigan Department of Natural Resources, Office of Land and Facilities