

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	D2
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 5 T 47N R 34W	I
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6					4		3		2			1
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

May 13 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (D2) Center of Section 5. Not established in the original survey.
- (1-Sec. 5) West 1/16 corner common to Section 5 T47N-R34W and Section 32 T48N-R34W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (D2) Established the corner at the intersection of straight lines connecting opposite Quarter corners.
- (1-Sec. 5) Established the corner midway between C1 and D1, 1319.60' West and East, and on the township line defined by same.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D2) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:	(1) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
11" W.Spruce N56E 34.3' "C1/4 BT"	7" Cedar N54E 5.65' "1/16S BT"
11" Cedar S66E 27.9' do	7" Cedar S62E 7.25' do
11" Maple S25E 10.5' do	6" Maple in clump S43W 11.6' do
10" W.Spruce N52W 24.2' do	6" Cedar N69W 20.9' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/1/04

For the Michigan Department of Natural Resources, Office of Land and Facilities