

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>04</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>8</u> T <u>47N</u> R <u>34W</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		●		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

May 18 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (D4) Center of Section 8. Not established in the original survey.
- (9-Sec. 8) East 1/16 corner, Section 8. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (D4) Established the corner at the intersection of straight lines connecting opposite Quarter corners.
- (9-Sec. 8) Established the corner midway and on a straight line between Center of Section 1310.49' West and Quarter corner 1310.49' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (D4) Set 1" IDx32" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in:
6" Maple S87E 22.3' "C1/4 BT"
10" Cedar S37E 29.4' do
4" Cedar S14E 14.3' do
12" Cedar N79W 37.7' do
Set sq'd cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag. | (9) Set 1" IDx32" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in:
10" Sugar N06E 24.2' "1/16S 8T"
12" Sugar N44E 24.7' do
9" Sugar S29E 5.4' do
8" Sugar N85W 11.5' do
Set sq'd cedar post adjacent. Bearings
are magnetic. Distances are to nail
with tag. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/1/04

For the Michigan Department of Natural Resources, Office of Land and Facilities