

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>C6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>8</u> T <u>47N</u> R <u>34W</u>	<u>6</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

C6 May 19 2004
 6 May 18 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17-18. Reestablished in 1966 by Billy D. Buckler, RLS, midway between Section corners and in the center of the Ford Road. Set 1.25"x30" Iron pipe (buried). 5" Y.Birch S40E 28.8', 6" Hard Maple S53W 44.6'.
 (6-Sec. 8) Northeast 1/16 corner. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) The 1966 monument was not recovered. Remonumented the 1966 position at record bearing and distance from the 1966 witnesses and in the center of the Ford Road. The Y. Birch NBT is in good condition with double overgrown blazes, and the Hard Maple NBT is now a 1' high stump with measuring notch visible. Distances north and south to adjacent section corners were found to be 2630.43' and 2625.87', respectively.
 (6-Sec. 8) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 12" W.Spruce N24E 48.3' "1/4S NBT" 5" Sugar NB1E 15.5' do 4" Maple N79W 35.8' do 12" Y.Birch S37E 28.9' overgrown blazes Drove the monument to 5" below the gravel surface. Bearings are magnetic. Distances are to nail with tag.	(6) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 4" Sugar N19E 6.3' "1/16S BT" 11" Sugar S89E 13.9' do 8" Sugar S09E 25.2' do 10" Sugar S18W 13.5' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/1/04

For the Michigan Department of Natural Resources, Office of Land and Facilities