

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>C5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>47N</u> R <u>34W</u>	<u>16</u>
	S <u>8</u> T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 19 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			●	●									
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C5) Corner common to Sections 7-8-17-18. Reestablished in 1966 by Billy D. Buckler, RLS: " Corner placed in center of Ford Road and on North edge of road to west, opposite a Ford Motor Company poster on a wood post (down), dated year 1941. Corner monument 1.25"x30" Iron pipe buried in center of Ford Road. Witnesses: 11" W.Pine S57E 50.1', 17" Hard Maple N70E 62.3'."
 (16-Sec. 8) East 1/16 corner between Sections 8-17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C5) The 1966 monument was not recovered. Remonumented the 1966 position at record bearing and distance from the 1966 witnesses and in the center of the Ford Road. The W.Pine is in good condition with overgrown blazes, the Maple is now a rotting 20" dia. stump with no markings visible.
 (16-Sec. 8) Established the corner on the Section line and midway between Quarter and Section corners 1309.58' West and East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 5" Sugar N59E 15.9' "S8 NBT" 6" Maple S43W 30.1' "S18 NBT" 8" Y.Birch N18W 50.2' "S7 NBT" 20" W.Pine S56E 50.5' with old blazes Bearings are magnetic. Distances are to nail with tag. Drove the monument to 5" below the gravel surface.	(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 3" Sugar S58E 9.7' "1/16S BT" 7" Sugar S16W 38.2' do 26" W.Pine S76W 59.4' do 3" Y.Birch N74W 19.7' do Set sq'd Spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/1/04

For the Michigan Department of Natural Resources, Office of Land and Facilities