

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>E3</u>
	T <u>47N</u> R <u>34W</u>	<u>E2</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 20 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5	•	4		3		2		1	
3				•								
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (E3) Corner common to Sections 4-5-8-9. Reestablished in 1974 by A.O.Enger, RLS by proportionate measurement between original W.Pine line tree stumps. Set 1"IDx36" iron pipe with 3.5" aluminum cap. NBTs: Sugar Maple 5 S89W 11.0', Red Maple 6 S32W 28.6', Red Maple 6 N05W 7.1'.
- (E2) Quarter corner common to Sections 4-5. Remonumented in 1974 by A.O.Enger, RLS, at the original position, which had been perpetuated by Billy D. Buckler, RLS, in 1966. Set 1"IDx36" iron pipe with 3.5" aluminum cap. NBTs: Red Maple 16 S15W 30.7', Red Maple 14 S52E 35.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (E3) Recovered the 1974 monument in good condition and at record bearing and distance from the 1974 witnesses, all in good condition, with the observation that the distances to the Sugar SW and the Red Maple SW appear to have been transposed in Mr. Enger's record. Made the monument firm in a mound of rock and made an additional NBT as described below.
- (E2) Recovered the 1974 monument in good condition and at record bearing and distance from the 1974 NBTs. The Maple SW is in good condition but the Maple SE is a rotting stump. Though Mr. Enger, in this record, states that he could not identify the original 8T W.Pine 6 S40W 20 links, noted in Mr. Buckler's earlier record, we recovered a rotting W.Pine stump, no marks visible, at proper bearing and distance. Also recovered another NBT, not of record, N60W, and noted below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| (E3) Found 1"ID iron pipe with 3.5" alum. State of Michigan cap. Blazed, scribed, and set measuring nails in:<br>9" Maple N04W 7.3' overgrown blazes *<br>8" Maple N88W 28.9' scribing visible *<br>9" Sugar S25E 11.2' overgrown blazes *<br>9" Sugar S77E 24.0' "S9 NBT"<br>Bearings are magnetic. Distances are to nail with tag. * denotes 1974 NBT, no new marks. | (E2) Found 1"ID I.pipe with 3.5" alum. State of Michigan cap. Blazed, scribed, and set meas. nails in:<br>4" Cherry N40E 4.6' "1/4S NBT"<br>13" Maple N60W 14.3' fd mrkd do<br>6" Cherry in clump S33E 25.0' do<br>20" Maple S19W 31.1' overgrown blazes *<br>Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1974 NBT no new marks. |
|--|---|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 7/1/04