

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>47N</u> R <u>34W</u>	<u>C3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>8</u> T <u>47N</u> R <u>34W</u>	<u>2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

C3 May 24 2004
 2 May 20 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3			●	●									
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C3) Corner common to Sections 5-6-7-8. 1852: Established by Z.B.Searles - [South] "corrected btwn Secs 5 & 6... 39.46 Set quarter section post... 79.46 Set post corner of Sects 5-6-7-8. Sugar 22 S54E 48 links, Sugar 24 N20W 24 links." Noted in 1966 record for C2 by Billy D. Buckler, RLS as having been used, along with C1 to reestablish C2 by proportionate measurement. No further record found. (2-Sec. 8) East 1/16 corner between Sections 5-8. Established in 1974 by A.O.Enger RLS, midway between Section and Quarter corners. Set 1"IDx36" iron pipe with 3.5" aluminum cap. BTs: B.Spruce 3 N07W 49.4', B.Spruce 3 S69E 34.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C3) Found no monumentation at the corner position. Reestablished the corner at Mr. Buckler's position by extrapolating from existing corners to the north and in the center of the Ford Road. Specifically, I reestablished the corner in the physical C/L of the road and a distance south of C2 which forms the same ratio to the original record of 40 chains as the ratio of the measured distance C1 to C2 forms with the original record of 39.46 chains. This position is 2632.33' south of C2, 2637.13' north of C4, and about 10' east of the proportionate position between A3 and E3.

(2-Sec. 8) Recovered the 1974 monument in good condition and at record bearing and distance from the remaining BT B.Spruce S65E. Made new witnesses as described below. Measured to Section and Quarter corners east and west and verified the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:	(2) Found 1"ID I.pipe with 3.5" alum. State of Michigan cap. Blazed, scribed, and set meas. nails in:
10" Y.Birch N32E 40.5' "S5 NBT"	4" B.Spruce S32E 8.8' "1/16S BT"
9" Sugar S68E 35.3' "S8 NBT"	5" Tamarack S66W 20.3' do
5" Sugar S58W 15.4' "S7 NBT"	6" B.Spruce N35W 27.3' do
6" Oak N84W 19.0' "S6 NBT"	4" B.Spruce S65E 34.3' overgrown blz *
Bearings are magnetic. Distances are to nail with tag.	Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1974 BT no new marks.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/1/04

For the Michigan Department of Natural Resources, Office of Land and Facilities