

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga
 (County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>47N</u> R <u>34W</u> | <u>C1</u> |
| | T <u>47N</u> R <u>34W</u> | <u>E6</u> |
| | T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

E6 Jun 29 2004
 C1 May 24 2004

A	B	C	D	E	F	G	H	I	J	K	L	M
1		●										
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17	●	16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C1) Corner common to Sections 5-6 T47N-R34W and 31-32 T48N-R34W. Established in 1846 by Austin Burt. "West on South Side Section 32...80.00 Set Sugar Post corner of Sections 31 and 32. Sugar 11 N52E 18, Sugar 14 N44W 39." Billy D. Buckler, RLS notes that he used this corner in 1966 to reestablish C2 by proportionate measurement. I found no mention of a monument at C1 in Buckler's notes.
 (E6) Quarter corner common to Sections 16-17. 1852: Established by ZB.Searles: [South] "corrected between Sections 16 & 17...40.00 Set quarter section post. Sugar 18 S73W 11 links, Sugar 10 N48E 30 links. ...80.00 Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C1) The original post and accessories were not recovered. Found and accepted a 3/4" iron pin buried about 6 ft. west of the center of the Ford Road, which checks reasonably well for distance north to an old fence at the north line of Section 31 T48N-R34W (79.97 ch R, 79.503 ch M) and south to recorded C2 (39.46 ch R, 39.345 ch M). Furthermore, the distance east to the re-monumented original D1 checks well with the record (40 ch R, 39.988 ch M), as does the distance west to the original B1 (40.00 ch R, 40.173 M). Left the monument in place and made witnesses as described below.

(E6) The original post and accessories were not recovered. Found no evidence of the original corner position on the ground. Reestablished the corner by single proportionate measurement to the original record between E5 and E7, 2632.72' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C1) Found 3/4" iron pin in the Ford Road. Blazed, scribed, and set measuring nails in:	(E6) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
11" Sugar N50W 26.4' "S31 NBT"	9" Sugar S82E 10.8' "1/4S NBT"
8" Maple N61E 72.3' "S32 NBT"	10" Sugar S10W 28.1' do
USGS Benchmark Mon. TT37C N87W 23.1'	8" Sugar S86W 21.2' do
4"x4"x5' tall phone box post S51E 37.9'	5" Sugar N07W 18.3' do
Bearings are magnetic. Distances to trees and post are to nails with tags.	Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/1/04

For the Michigan Department of Natural Resources, Office of Land and Facilities