

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| <u>Baraga</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S 13 T 47N R 34W _____ | 10 |
| | S 12 T 47N R 34W _____ | 12 |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M | | | |
|----|----|---|---|---|---|---|----|---|---|----|---|---|----|----|----|----|
| 1 | | | | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | | 3 | | | 2 | 1 | | |
| 3 | | | | | | | | | | | | | | | | |
| 4 | 7 | | | | | | 8 | | | 9 | | | 10 | 11 | 12 | |
| 5 | | | | | | | | | | | | | | | | |
| 6 | 18 | | | | | | 17 | | | 16 | | | 15 | | 14 | 13 |
| 7 | | | | | | | | | | | | | | | | |
| 8 | 19 | | | | | | 20 | | | 21 | | | 22 | | 23 | 24 |
| 9 | | | | | | | | | | | | | | | | |
| 10 | 30 | | | | | | 29 | | | 28 | | | 27 | | 26 | 25 |
| 11 | | | | | | | | | | | | | | | | |
| 12 | 31 | | | | | | 32 | | | 33 | | | 34 | | 35 | 36 |
| 13 | | | | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 12 08/24/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 13) South 1/16 between Sections 13 and 14. 1980 - Established by K.L.Sackett RLS midway and on line between corners north and south. Set 1"IDx32" iron pipe with 4" alum. cap. 8" Sugar N47E 14.6', 6" Sugar S25E 23.3', 14" Cedar S29W 3.4'.

(12-Sec. 12) South 1/16 corner, Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 13) Found the 1980 monument in good condition and at record bearing and distance from the BT Cedar SW, in good condition. The Sugars NE and SE are not apparent above the snowline. Verified the position of the monument and accepted same as a careful and faithful establishment of the position of the corner.

(12-Sec. 12) Established the corner midway and on a straight line between Quarter corner 1322.99' south and the Intersection of 1/4 lines of Section 12 1322.99' north.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 16" Cedar S34W 3.5' marks visible 1980 BT
 8" Sugar N35E 13.8' mrkd "1/16S BT"
 7" Sugar S60E 17.8' do
 17" Y.Birch West 22.1' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Sugar N44E 33.45' mrkd "1/16S BT"
 13" Sugar S66E 27.65' do
 10" Sugar S05W 5.8' do
 4" Sugar S81W 31.9' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/22/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities