

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	M7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 2 T 47N R 34W	1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 1 12/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M7) Section corner common to Sections 13-24 T47N-R34W and Sections 18-19 T47N-R33W. 1846 - Established by Austin Burt, Deputy Surveyor. Set Cedar post. Cedar 20" S27W 21 links, Cedar 14" N28E 14 links. 1966 - Remonumented by Billy D. Buckler RLS: Replaced corner at wood post. Found two probable bearing trees, down and in poor condition; S37[sic]W, 21 links and N28E 14 links. Set 1"ID I.pipe with 4" aluminum cap. 9" Balsam N30E 13.5', 8" B.Spruce S23E 23.0', 6" B.Spruce N45W 45.5'. Rec. Liber 2 of LCRC, Page 336.

(1-Sec. 2) West 1/16 between Section 2 T47N-R34W and Section 35 T48N-R34W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M7) Found the 1966 monument in good condition and at record bearing and distance from the 1966 NBTs. The Balsam NE and Spruce SE are dead and down. The Spruce NW is a dead stub. The "probable bearing trees" were not observed due to snow cover. Accepted the monument as the best available evidence of the position of the original corner.

(1-Sec. 2) Established the corner midway and on the Township line between Section corner 1323.82' west and Quarter corner 1323.82' east. The position for the corner falls in a rocky location and the monument is set in a rock-filled void. The center of the cap marks the position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M7) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 5" Balsam S47E 11.25' mrkd "S19 NBT"
 6" W.Birch S21E 12.1' do
 10" B.Spruce S08W 29.85' "S24 NBT"
 5" Maple N56W 33.4' "S13 NBT"
 Sq'd cedar post adjacent.
 Bearings are magnetic.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Maple N80E 11.75' mrkd "1/16S BT"
 8" Cedar S68E 38.8' do
 9" Hemlock S49W 14.95' do
 12" Y.Birch N50W 19.0' do
 Bearings are magnetic.
 Set sq'd cedar post adjacent.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/22/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities