

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	L5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 13 T 47N R 34W	16
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on L5 03/05/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(L5) Quarter corner common to Sections 12-13. 1852 - Established by Z.B.Searles Deputy Surveyor on the Section line between Section corners 39.985 chains east and west. Set post. Fir 6" S50E 11 links, W.Pine 30" N70W 12 links. May 1958 - L2 P210, J.P.Smallwood RLS found 6" sq'd cedar post. 10" W.Birch N85W 17.72', 8" Cedar N15E 16.01', 4" Maple N55W 16.32'. 1979 - L1 P376, K.L.Sackett RLS found 1.5" I.D. Iron pipe witnessed by M.S.H.D., which fit well with corners to east and west. Witnesses: 6" Maple N52W 16.4', 12" Maple S35E 26.4', 14" W.Pine S25W 50.8'.

(16-Sec. 13) East 1/16 corner between Sections 13 and 24. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L5) Recovered a 1.5" O.D. iron pipe in good condition and at record bearing and distance from the 1979 witness Maple NW, now a dead stub. No evidence of the remaining two NBTs was apparent above the snow. Accepted the monument as the best available evidence of the position of the original corner.

(16-Sec. 13) Established the corner midway and on the Section line between Section corner 1328.89' east and Quarter corner 1328.89' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L5) Found 1.5" O.D. iron pipe.
 Set measuring nail with MDNR tag in the side of:
 14" Maple N66E 20.3' mrkd "1/4S NBT"
 3" W.Spruce S31E 15.2' do
 6" Maple in clump N86W 20.0' do
 6" Spruce N65W 16.4' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 6" Tamarack N70E 22.2' mrkd "1/16S BT"
 8" B.Spruce S23E 28.5' do
 7" B.Spruce S50W 16.3' do
 6" B.Spruce S86W 22.0' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/22/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities

16297
16309