

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	K6
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 13 T 47N R 34W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14	●	13	
7											●		
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on K6 03/05/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K6) Quarter corner common to Sections 13 and 14. 1852 - Established by Z.B.Searles Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. 1980 - Reestablished by K.L.Sackett RLS. Original monument and accessories not found. Restored midway and on line between section corners north and south. Set 1"IDx32" I.pipe with 4" alum. cap. 12" Sugar S57W 24.1', 12" Sugar N62W 16.0', 8" Sugar N54E 40.1'. Rec. Liber 4 of LCRC, Page 33.

(11-Sec. 13) Southwest 1/16 corner, Section 13. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K6) Found the 1980 monument in good condition and at record bearing and distance from the 1980 witnesses. The Sugar NE is a dead stub. The Sugars SW and NW are in good condition with scribing visible. Verified the position of the monument with respect to Section corners north and south and accepted same as a careful and faithful reestablishment of the position of the original corner.

(11-Sec. 13) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K6) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 14" Sugar S58W 24.7' old marks 1980 NBT
 14" Sugar N62W 16.8' do do
 15" Sugar South 29.2' mrkd "1/4S NBT"
 12" Sugar N21W 22.2' do do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" B.Spruce S76E 30.8' mrkd "1/16S BT"
 4" Balsam S33E 7.8' do do
 7" B.Spruce S21W 31.0' do do
 7" B.Spruce S67W 20.5' do do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/22/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities