

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	K5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 13 T 47N R 34W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 5 08/25/2009 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(K5) Corner common to Sections 11-12-13-14. 1852 - Established by Z.B.Searles Deputy Surveyor. Set post. Spruce 10" S31E 17 links, Spruce 12" N87 1/2W 41 links. March 1958 - L2 P211, J.P.Smallwood RLS found 4" sq'd spruce post. 5" Spruce S65E 14.00', 6" Spruce East 16.35', 9" Spruce N05E 16.40'. 1979 - L1 P377, Reestablished by K.L.Sackett RLS from M.S.H.D. stationing and R.O.W. markers. Set 1"IDx36" iron pipe with 4" alum. cap in sphagnum moss area. No available NBTs. Corner falls 45.15' west of US 141 and Sta. 1640 + 13.83. R.O.W. Marker West 54.8'.

(5-Sec. 13) North 1/16 corner, Section 13. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K5) Recovered the 1979 monument disturbed, bent over and flush to ground. Recovered the base of the monument, plumb and apparently in the original position, at substantial record bearing and distance from the R.O.W. Marker to the west. Accepted the position as the best available evidence of the position of the original corner.

(5-Sec. 13) Established the corner midway and on a straight line between Quarter corner 1297.26' north and the intersection of 1/4 lines of Section 13, 1297.26' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 5" Tamarack S40W 26.1' mrkd "S14 NBT"  
 5" Tamarack N89W 22.05' "S11 NBT"  
 3" B. Spruce N44W 21.9' "S11 NBT"  
 Conc R/W marker is N87W 54.8' to WEST face.  
 Bearings are magnetic.  
 Set sq'd post adjacent.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 2" Maple S11W 1.65' mrkd "1/16S BT"  
 3" Maple N69W 11.3' do  
 3" Maple N23W 8.85' do  
 3" Spruce S74E 26.65' do  
 Set sq'd Cedar post adjacent.  
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski* Date 09/22/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

