

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>27</u> T <u>47N</u> R <u>34W</u>	<u>13</u>
	S <u>27</u> T <u>47N</u> R <u>34W</u>	<u>14</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 14 10/15/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (13-Sec. 27) Southeast 1/16 corner, Section 27. Not established in the original survey.
- (14-Sec. 27) South 1/16 corner between Sections 26 and 27. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (13-Sec. 27) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (14-Sec. 27) Established the corner midway and on the Section line between Section corner 1315.08' south and Quarter corner 1315.08' north.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |  |
|---|--|
| (13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:<br>5" W.Birch North 3.1' mrkd "1/16S BT"<br>9" Cedar N39E 6.8' do<br>6" W.Birch S56E 19.8' do<br>13" Cedar S05E 10.4' do<br>Set sq'd cedar post adjacent.<br>Bearings are magnetic. | (14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:<br>15" R.Maple N30E 17.1' mrkd "1/16S BT"<br>7" Cedar S41E 51.7' do<br>4" Sugar S43W 30.4' do<br>9" Sugar N70W 20.5' do<br>Set sq'd cedar post adjacent.<br>Bearings are magnetic. |
|---|--|

Signed by Stephan J. Szyszkoski Date 10/27/2009  
 Surveyor's Michigan License No. 33986  
 For the Michigan Department of Natural Resources, Office of Land and Facilities

