

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	I11
	T 47N R 34W	I12
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on I11 10/15/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I11) Corner common to Sections 26-27-34-35. 1977 - K.L.Sackett RLS reestablished the corner. 2001 the undersigned recovered the 1977 monument and made new witnesses: Found 1"ID I.pipe with 4" aluminum MDNR cap. 9" dbl Maple S68E 43.3', 9" W.Spruce S44W 88.7', 6" Maple N32W 51.0', 9" Maple N77E 10.6' (1977 witness).

(I12) Quarter corner common to Sections 34 and 35. 1977 - K.L.Sackett RLS reestablished the corner midway and on line between Section corners. Set 1"IDx36" iron pipe with 4" aluminum cap. 6" Maple S48E 32.1', 10" Cherry S83W 20.6', 7" Elm N26E 24.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I11) Found the 1977 monument in good condition and at record bearing and distance from the witnesses of record. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(I12) Found the 1977 monument in good condition, at the record position between Section corners, and at record bearing and distance from the 1977 NBT Cherry S83W, in good condition with overgrown blazes. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" dbl Maple N78E 10.7' old blazes 1977 NBT
 7" Maple N31W 51.4' scribing visible 2001 NBT
 10" Maple S67E 43.8' do do
 4" Balsam S20W 8.1' mrkd "S34 NBT"
 Bearings are magnetic.

(I12) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 15" Cherry S87W 21.05' old blazes 1977 NBT
 6" Sugar N6E 5.2' mrkd "1/4S NBT"
 5" Sugar N77E 6.0' do do
 7" Sugar S36E 28.65' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/27/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities