

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	113
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 35 T 47N R 34W	16
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 113 10/15/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(I13) Corner common to Sections 34-35 T47N-R34W and Sections 2-3 T46N-R34W. 1977 - K.L.Sackett RLS reestablished the corner on line between corners east and west. Set 1"IDx36" I.pipe with 4" aluminum cap. 9" Sugar N76W 19.2', 8" Sugar N89E 16.0', 8" Sugar S15E 33.9'.

(16-Sec. 35) East 1/16 corner between Section 35 T47N-R34W and Section 2 T46N-R34W. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I13) Found the 1977 monument in good condition and at record bearing and distance from the 1977 Sugar N89E 16.0' and the 1977 Sugar S15E 33.9'. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(16-Sec. 35) Established the corner midway and on the Township line between Quarter corner 1317.84' west and Section corner 1317.84' east.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I13) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 11" Sugar East 16.1' old blazes 1977 NBT  
 12" Sugar S10E 34.1' do do  
 5" Y.Birch S64W 32.75' mrkd "S3 NBT"  
 5" Y.Birch N58W 25.2' "S34 NBT"  
 Bearings are magnetic.

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" Y.Birch N73E 26.45' mrkd "1/16S BT"  
 9" Cedar S43E 25.2' do  
 13" Cedar S35W 22.45' do  
 13" Cedar N61W 21.0' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/27/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

