

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 4 T 47N R 34W	7
	S 4 T 47N R 34W	6
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 6 10/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 4) North 1/16 corner between Sections 3 and 4. Not established in the original survey. The original plat for this township gives distances 19.51 chains north to Section corner and 20.00 chains south to Quarter corner.

(6-Sec. 4) Northeast 1/16 corner, Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 4) Established the corner 20 chains, proportionate to the original record and on the Section line between Section corner 1283.67' north and Quarter corner 1315.90' south.

(6-Sec. 4) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 9" Sugar N76E 1.55' mrkd "1/16S BT" 13" Sugar S15E 14.25' do 6" Sugar S84W 22.75' do 10" Sugar N21W 26.15' do Set sq'd cedar post adjacent. Bearings are magnetic.	(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 16" Y.Birch N01E 25.2' mrkd "1/16S BT" 16" Sugar S89E 17.0' do 18" Sugar S19W 14.4' do 14" Sugar S53W 9.5' do Set sq'd cedar post adjacent. Bearings are magnetic.
---	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/03/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities

16179
16180