

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	G3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3							●						
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

I, Stephan J. Szyszkoski, in a field survey on 10/28/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G3) Corner common to Sections 3-4-9-10. 1852 - Established by Z.B.Searles Deputy Surveyor. Set post. Y.Birch 12" S64E 35 links, Cedar 18" N40W 9 links. 1966 - Remonumented by Billy D. Buckler RLS: "Replaced corner at old wood post. Found remains of a cedar stump (probable bearing tree) N40W 09 links. Location poster placed by Ford Motor Co. men and a register tree with several signatures". Set 1" pipe with 4" aluminum cap. 8" Hard Maple N73W 5.0', 9" Y.Birch S37E 33.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G3) Recovered the 1966 monument in good condition and at record bearing and distance from the 1966 accessories. The Y.Birch SE is a dead stub, the Hard Maple NW is in good condition with overgrown blazes. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G3) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap.
 Set measuring nail with MDNR tag in the side of:
 9" Sugar N63W 4.95' old blazes 1966 NBT
 5" Sugar N47E 29.3' mrkd "S3 NBT"
 10" Sugar S80E 17.0' "S10 NBT"
 9" Sugar S29W 34.6' "S9 NBT"
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/03/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities