

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T <u>47N</u> R <u>34W</u>	<u>8</u>
	S <u>4</u> T <u>47N</u> R <u>34W</u>	<u>F2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5				3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

I, Stephan J. Szyszkoski, in a field survey on 8 10/21/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 4) West 1/16 corner, Section 4. Not established in the original survey.

(F2) Center of Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 4) Established the corner midway and on a straight line between Quarter corner 1327.36' west and Center of Section 1327.36' east.

(F2) Established the corner at the intersection of straight lines connecting opposite quarter corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 14" Tamarack S85E 39.15' mrkd "1/16S BT"
 9" Spruce S18W 14.4' do
 9" Spruce S86W 29.65' do
 7" Balsam N05E 29.9' do
 Set sq'd cedar post adjacent. Metal fence post adjacent. Bearings are magnetic.

(F2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Cedar N03E 19.3' mrkd "C1/4 BT"
 12" Cedar N76E 10.8' do
 14" Cedar S59W 10.9' do
 18" Cedar N42W 26.7' do
 Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/03/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities