

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 34W	I1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1									●				
2	6			5				4		3		2	1
3													
4	7			8				9		10		11	12
5													
6	18			17				16		15		14	13
7													
8	19			20				21		22		23	24
9													
10	30			29				28		27		26	25
11													
12	31			32				33		34		35	36
13													

I, Stephan J. Szyszkoski, in a field survey on 08/13/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I1) Corner common to Sections 2-3 T47N-R34W and Sections 34-35 T48N-R34W. 1846 - Established by Austin Burt Deputy Surveyor. Set Tamarack post. Cedar 8" N20E 15 links, Tamarack 6" N12W 16 links. 1852 - Additional BTs by Z.B.Searles Deputy Surveyor: Spruce 4" S23 1/2E 17 links, Spruce 4" S32 1/4W 18 links. 1957 - Billy D. Buckler RLS recovered the BT Spruce S32W 18 links in good condition with boulder and wood post in place and with Ford Motor Co. location poster at corner. Set 1" pipe with 4" brass cap. 8" Cedar S40E 21 links, 6" Cedar S42W 41 links, 12" W.Pine N78E 68 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I1) Found the 1957 monument in good condition and at record bearing and distance from the 1957 witnesses. The W.Pine and Cedar SW are in good condition with overgrown blazes. The Cedar SE is a dead stub. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I1) Fd. 1"ID I.pipe with 4" alum. brass Mich. Dept. of Conservation cap.
 Set measuring nail with MDNR tag in the side of:
 18" W.Pine N82E 45.8' old blazes 1957 NBT
 10" Cedar S42W 27.1' do do
 10" Cedar N23E 5.0' mrkd "S35 NBT"
 12" Y.Birch S74W 8.2' "S3 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/03/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995