

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 N.R. 30 & 31 W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 1, T48N R3W and 6, T48N R30W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/22/65 with J Magnuson

WITNESSES TO CORNER..... 16" H. Maple (1/4S NBT), N 72° E, 32 1/2 Dks.



14" H. Maple (1/4S NBT), S 07° W, 10 Dks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed at Wood Post which checks with (W. Pine 52" S 30° W, 30 Dks.) now a charred stub with upper face and iron marks visible and portion of lower face and iron marks present.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/13/1965
REGISTERED LAND SURVEYOR