

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 N.R. 31 W


Baraga COUNTY

DESCRIPTION OF CORNER 1/4 Corner for Secs. 15-14

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 8/2/65 with Forester Stevens

WITNESSES TO CORNER..... 8" H. Maple (1/4S NBT), N 45° E, 36 1/2 Lks.



8" H. Maple (1/4S NBT), S 66° W, 20 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from (Sugar 12", N 15° W, 38 Lks.), Original BT, now a dead 6" stub with scribe marks visible on upper face but in poor condition. BT to SW is gone.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 2/11/1966  
Frank J. Bray  
REGISTERED LAND SURVEYOR