

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 48N R 31W	C2	
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____		
	S 24 T 48N R 31W	PCC N. of #16	
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	●	5		4		3		2				1
3													
4	7		8		9		10		11				12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													●
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

I, Stephan J. Szyszkoski, in a field survey on C2 03/17/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C2) Quarter corner common to Sections 5 and 6. 1848 - Established by Wells Burt, Deputy Surveyor on the Section line between Section corner 40.00 chains south and Section corner on the Township line 39.20 chains north. Set Sugar post. Y.Birch 8 N36E 53 links, Y.Birch 12 S36W 39 links.

(PCC N. of #16) Intersection of the Easterly N-S 1/16 line of Sec. 24 with the southerly R/W line (50.00' as measured at right angles from the track centerline) of the former DSS&A Railway. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C2) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner on the Section line between Section corners 2639.68' south and 2586.88' north, being proportionate to the original record.

(PCC N. of #16). Monumented the corner on a straight line between monumented 1/16 corner #16, Section 24 and unmonumented 1/16 corner #13, Section 24, at its intersection with the southerly RR R/W line, said intersection being 819.04' north of 1/16 corner #16 as measured along the 1/16 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Sugar N33E 7.3' mrkd "1/4S NBT"  
 16" Y.Birch S58E 11.05' do  
 8" Sugar S15W 11.55' do  
 11" Sugar N84W 23.3' do  
 Bearings are magnetic.  
 Set sq'd Cedar post adjacent.

(PCC N. of #16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Balsam N25W 20.55' mrkd "PCC BT"  
 8" Balsam N54E 16.15' do  
 9" W.Pine S26E 30.8' do  
 6" Balsam S23W 9.8' do  
 Bearings are magnetic.  
 Set sq'd Cedar post adjacent.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/25/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Management