

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>48N</u> R <u>31W</u>	<u>16</u>
	S <u>24</u> T <u>48N</u> R <u>31W</u>	<u>PCC N. of L9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on PCC 03/16/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(16-Sec. 24) East 1/16 corner between Sections 24 and 25. Not established in the original survey.

(PCC N. of L9) Intersection of the N-S 1/4 line of Section 24 with the southerly R/W line (50.00' as measured at right angles from the track centerline) of the former DSS&A Railway. Not previously monumented.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(16-Sec. 24) Established the corner midway and on the Section line between Quarter corner 1324.68' west and Section corner 1324.68' east.

(PCC N. of L9) Monumented the corner at the intersection of the N-S 1/4 line of Section 24 and the southerly RR R/W line, being 1076.39' north of Quarter corner L9, as measured along the 1/4 line.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Spruce S69E 16.55' mrkd "1/16S BT"  
 13" Maple S01E 15.75' do  
 7" Maple S88W 18.6' do  
 8" twin Maple N29W 17.4' do  
 Bearings are magnetic.  
 Set sq'd Cedar post adjacent.

(PCC N. of L9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 4" Spruce N70E 44.1' mrkd "PCC BT"  
 4" Cedar S48E 26.15' do  
 4" Cedar S04E 28.05' do  
 5" Cedar S64W 38.6' do  
 Bearings are magnetic.  
 Set sq'd Cedar post adjacent.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/25/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Management

16385  
16383