

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	J7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 23 T 48N R 31W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7										●			
8	19		20		21		22		23		24		
9										●			
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 12 11/19/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J7) Quarter corner common to Sections 14 and 23. 1975 - Reestablished by K.L.Sackett RLS on line between Section corner east and proportion position in Coon Lake west. Set 1"IDx36" Iron pipe with 4" aluminum cap. 13" Sugar N15W 21.9', 10" Y.Birch S75W 4.9'.

(12-Sec. 23) South 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J7) Found the 1975 monument in good condition and at record bearing and distance from the 1975 witnesses. The Y.Birch SW is in good condition with overgrown blaze. The Sugar NW is a dead 12' high stub with scribing visible. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(12-Sec. 23) Established the corner midway and on a straight line between Quarter corner 1343.89' south and Center of Section 23 1343.89' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J7) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Sugar N20E 21.8' mrkd "1/4S NBT"
 19" Y.Birch S09E 22.8' do
 9" Sugar N57W 27.0' do
 Set nail/tag in root of the 1975 NBT:
 11" Y.Birch S84W 4.75' old blaze
 Bearings are magnetic. Set post adjacent.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Sugar N22E 13.1' mrkd "1/16S BT"
 5" Sugar South 21.0' do
 14" Sugar S61W 14.7' do
 12" Sugar N63W 18.5' do
 Constructed small rock mound around monument.
 Bearings are magnetic. Set post adjacent.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/25/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Titles

16381
16382