

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 6 T 48N R 31W	B2
	S 6 T 48N R 31W	16
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		●		5		4		3		2		1	
3		●											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on B2 03/17/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B2) Center of Section 6. Not established in the original survey.

(16-Sec. 6) East 1/16 corner between Sections 6 and 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(16-Sec. 6) Established the corner midway and on the Section line between Quarter corner 1338.09' west and Section corner 1338.09' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Y.Birch N02E 4.4' mrkd "C1/4 BT"  
 7" Cedar N84E 13.7' do  
 10" Maple S05E 8.45' do  
 4" Hemlock N83W 17.0' do  
 Bearings are magnetic.  
 Set sq'd Cedar post adjacent.

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Sugar N35E 11.85' mrkd "1/16S BT"  
 9" twin Sugar S56E 28.6' do  
 5" Sugar S22W 15.25' do  
 4" Sugar N76W 16.3' do  
 Bearings are magnetic.  
 Set sq'd Sugar post adjacent.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/25/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Management

16387

16388