

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>48N</u> R <u>31W</u>	_____ 13
	S <u>6</u> T <u>48N</u> R <u>31W</u>	_____ 12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3		●	●										
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 13 03/18/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (13-Sec. 6) Southeast 1/16 corner, Section 6. Not established in the original survey.
- (12-Sec. 6) South 1/16 corner, Section 6. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (13-Sec. 6) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (12-Sec. 6) Established the corner midway and on a straight line between Quarter corner 1315.91' south and Center of Section 6 1315.91' north.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |   |
|---|---|
| (13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>7" Sugar N59E 17.2' mrkd "1/16S BT"<br>9" twin Sugar S35E 6.15' do<br>4" Sugar S37W 14.85' do<br>12" Sugar N57W 7.2' do<br>Bearings are magnetic.<br>Set sq'd Balsam post adjacent. | (12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>6" Maple N77E 1.0' mrkd "1/16S BT"<br>7" Sugar S06W 6.45' do<br>4" Hemlock N73W 18.45' do<br>15" Maple N29W 6.6' do<br>Bearings are magnetic. |
|---|---|

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/25/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Management

16389  
16390