

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	B1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 6 T 48N R 31W	10
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1		●											
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on B1 03/22/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B1) Quarter corner common to Section 6 T48N-R31W and Section 31 T49N-R31W. 1846 - Established by John Burt, Deputy Surveyor on the Township line between Section corner 40.00 chains east and Township corner 37.46 chains west. Set Maple post. Sugar 6 N77E 37 links, Sugar 16 N30W 16 links.

(10-Sec. 6) South 1/16 corner between Section 6 T48N-R31W and Section 1 T48N-R32W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B1) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner on the Township line between Section corner 2630.03' east and Township corner 2463.03' west, being proportionate to the original record.

(10-Sec. 6) Established the corner midway and on the Range line between Section corner 1310.47' south and Quarter corner 1310.47' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" twin Hemlock N12E 21.65' mrkd "1/4S NBT"
 6" Sugar S85E 19.45' do
 7" twin Y.Birch S14E 9.85' do
 6" Hemlock S82W 7.6' do
 Bearings are magnetic.
 Set sq'd Cedar post adjacent.

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Cedar S77E 5.95' mrkd "1/16 BT"
 4" Balsam S42E 17.65' do
 9" Cedar S12W 14.45' do
 3" Cedar N70W 11.5' do
 Bearings are magnetic.
 Set sq'd Cedar post adjacent.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/25/2010



For the Michigan Department of Natural Resources and Environment, Office of Land and Water Management