

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	16
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 15 T 48N R 31W	9
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 9 04/22/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I6) Quarter corner common to Sections 14 and 15. 1965 - F.J.Bray RLS remonumented the corner at record bearing and distance from an original BT Sugar 12" N15W 38 links, found by him as a dead 6' stub with scribe marks visible on upper face, in poor condition. Set 1" I.pipe with 4" alum. cap at the corner position. 8" H.Maple N45E 36.5 links, 8" H.Maple S66W 20 links.

(9-Sec. 15) East 1/16 corner, Section 15. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I6) Found the 1965 monument in good condition and at record bearing and distance from the remaining 1965 NBT Sugar NE, in good condition with scribing visible. The NBT Sugar SW was not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(9-Sec. 15) Established the corner midway and on a straight line between Quarter corner 1311.38' east and Center of Section 15 1311.38' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I6) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 9" Sugar N50E 24.4' marks visible (1965 NBT)
 8" Sugar S41E 23.15' mrkd "1/4S NBT"
 4" Sugar S87W 5.95' do
 7" Sugar N04E 23.05' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Sugar N10W 16.55' mrkd "1/16S BT"
 6" Maple S89E 3.15' do
 5" Y.Birch S45W 16.25' do
 9" Y.Birch N48W 16.95' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/07/2010



For the Michigan Department of Natural Resources and Environment, Forest Management