

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	H7
	T 48N R 31W	I4
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10	●	11		12		
5													
6	18		17		16		15		14		13		
7								●					
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on I4 05/11/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented; recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H7) Quarter corner common to Sections 15 and 22. 1848 - Established by Wells Burt Deputy Surveyor midway and on the Section line between monumented Section corner G7 39.88 chains west and unmonumented Section corner I7 39.88 chains east. Set Y.Birch post. Cedar 18 S86E 28 links, Cedar 8 N85W 14 links.

(I4) Quarter corner common to Sections 10-11. 1848 - Established by Wells Burt Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set Sugar post. Sugar 9 S27E 27 links, Sugar 8 N69W 37 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H7) The original post and accessories were not recovered. The original Meander Corner on the west shore of Coon Lake was not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2633.28' east and west. The position for Section corner I7 falls in Coon Lake and is not monumented. For the purpose of the establishment of H7, the position of I7 was computed by double proportionate measurement to the original record between corners G7, J7, I6, and I8.

(I4) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2603.72' north and south, proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Cedar N46W 15.5' mrkd "1/4S NBT"
 8" Cedar N53E 18.25' do
 3" Cedar S14E 21.7' do
 3" twin Cedar S20W 18.0' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

(I4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Balsam N14W 9.2' mrkd "1/4S NBT"
 7" Sugar N80E 28.3' do
 6" Sugar S08E 5.7' do
 9" Sugar S88W 22.6' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/07/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

