

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	H5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S 10 T 48N R 31W	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2			1
3													
4	7		8		9			10		11			12
5													
6	18		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

I, Stephan J. Szyszkoski, in a field survey on 8 05/03/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H5) Quarter corner common to Sections 10-15. 1848 - Established by Wells Burt Deputy Surveyor midway and on the Section line between Section corners 40.02 chains east and west. Set Cedar post. Y.Birch 12 N49W 36 links, Y.Birch 14 S17E 39 links. 1957 - Dean C. DeLaMater RLS searched for this corner on behalf of the Michigan Dept. of Conservation and found no evidence.

(8-Sec. 10) West 1/16 corner, Section 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H5) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2639.71' east and west, proportionate to the original record. The position for the corner falls in the intersection of skid roads SE, SW and NW. The monument projects 7" above grade (at refusal) and a 5" dia. Cedar post adjacent for a marker.

(8-Sec. 10) Established the corner midway and on a straight line between Quarter corner 1315.70' west and Center of Section 1315.70' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 3" Balsam N26E 33.1' mrkd "1/4S NBT"
 3" Poplar N73E 23.8' do
 3" twin Poplar S53E 15.7' do
 3" Balsam S02E 20.8' do
 Sq'd cedar post adjacent.
 Bearings are magnetic.

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 4" Maple in clump N89E ---- mrkd "1/16S BT"
 6" Y.Birch S21E 9.8' do
 6" Spruce S12W 11.6' do
 4" Y.Birch N26W 4.75' do
 Set sq'd cedar post N'ly 0.5' (no nail)
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/07/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division