

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	J5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 14 T 48N R 31W	5
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 5 04/28/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J5) Quarter corner common to Sections 11 and 14. 1848 - Established by Wells Burt Deputy Surveyor midway and on the Section line between Section corners 40.02 chains east and west. Set maple post. Spruce 12 S34E 36 links, Spruce 14 N25W 28 links. 1957 - Dean C. DeLaMater RLS searched for this corner on behalf of the Michigan Dept. of Conservation and found no evidence.

(5-Sec. 14) North 1/16 corner, Section 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corner I5 2639.68' west and Section corner K5 2639.68' east, proportionate to the original record. The position used for K5 is in Nelligan Lake and is not monumented. Its position was determined by extending the East line of Section 11 southerly by the record distance (586.84') from the Witness Corner to the Meander Corner on the north shore of Nelligan Lake, monumented by R.Schmeling RLS and recorded in Liber 4, Page 116, Land Corner Records, Baraga County.

(5-Sec. 14) Established the corner midway and on a straight line between Quarter corner 1294.85' north and the intersection of 1/4 lines of Section 14 1294.85' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 5" R.Pine N06E 12.9' mrkd "1/4S NBT"  
 5" Tamarack S82E 7.75' do  
 6" Tamarack N78W 14.3' do  
 5" Tamarack S03E 3.05' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" Cedar N26E 14.4' mrkd "1/16S BT"  
 5" Spruce S13E 6.8' do  
 5" Tamarack S52W 21.35' do  
 4" Spruce N32W 25.2' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 07/07/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division