

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	K6
	T R	
	T R	
2. Property Controlling in Section	S 14 T 48N R 31W	3
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5		4		3		2		1			
3													
4	7	8		9		10		11		12			
5													
6	18	17		16		15		14		13			
7													
8	19	20		21		22		23		24			
9													
10	30	29		28		27		26		25			
11													
12	31	32		33		34		35		36			
13													

I, Stephan J. Szyszkoski, in a field survey on 3 04/22/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K6) Quarter corner common to Sections 13-14. 1848 - Established by Wells Burt Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set Spruce post. Y.Birch 18 S47E 17 links, Y.Birch 10 N50W 64 links. Found no subsequent record.

(3-Sec. 14) North 1/16 corner between Sections 14 and 15. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K6) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corner K7 2576.00' south and Section corner K5 2576.00' north, proportionate to the original record. The position for K5 is in Nelligan Lake and is not monumented. Its position was determined by extending the East line of Section 11 southerly by the record distance (586.84') from the Witness Corner to the Meander Corner on the north shore of Nelligan Lake, monumented by R.Schmeling RLS and recorded in Liber 4, Page 116, Land Corner Records, Baraga County.

(3-Sec. 14) Established the corner midway and on the Section line between Section corner 1302.01' north and Quarter corner 1302.01' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 3" Sugar N47E 18.55' mrkd "1/4S NBT"
 8" Sugar S30W 21.1' do
 12" Y.Birch S75W 6.55' do
 6" Maple N41W 42.65' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 14" Cedar S86E 25.45' mrkd "1/16S BT"
 6" Spruce S37W 20.95' do
 10" twin Y.Birch S55W 14.25' do
 3" Sugar N74W 13.45' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/07/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division