

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 31W	G5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S 15 T 48N R 31W	6
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●		●				
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 6 04/22/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (G5) Corner common to Sections 9-10-15-16. 1984 - Alan K. Pierce RLS recovered a Michigan Dept. of Conservation monument placed by F.J.Bray RLS in 1965, set at record bearing and distance from a Y.Birch OBT and remains of a Cedar OBT. 1984 record states: Found iron pipe with brass cap witnessed by PK nail in 20" Y.Birch S28W 9.56', 12" Cedar N58W 30.82', 8" Spruce North 12.58', 6" Cedar S70E 11.21'.

(6-Sec. 15) Northeast 1/16 corner, Section 15. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (G5) Found the Michigan Dept. of Conservation monument in good condition and at record bearing and distance from the Cedar NW and Cedar SE NBTs, in good condition. The Cedar NW NBT was one of the two marked by Mr. Bray in 1965. The Y.Birch SW NBT is now a standing dead stub 25' tall, the NBT Spruce North is a rotting stump, both at record bearing and distance. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(6-Sec. 15) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (G5) Found 1"ID I.pipe with 4" MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 6" Sugar N40E 12.75' mrkd "S10 NBT"
 6" Maple S25W 4.95' "S16 NBT"
 The record NBTs found as follows:
 12" Cedar N59W 30.8' PK nail
 8" Cedar S68E 11.2' do
 Bearings are magnetic.
 (6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Maple N25E 12.8' mrkd "1/16 BT"
 11" Y.Birch S56E 17.15' do
 16" Hemlock S10E 20.3' do
 10" Cedar S55W 25.15' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 07/07/2010
 Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources and Environment, Forest Management Division